

Computer Room Open Floor Tile Work Rules

The removal of floor tiles to perform work in a raised floor environment can create a serious safety hazard. We know this from experience. One individual sustained injuries falling into an unmarked open floor tile and another almost fell into one. Luckily, the injuries were not serious. We must prevent this from happening again. It is imperative to properly define a work area containing open tiles by using safety markers. For this purpose, we have provided bright yellow safety cones as well as the traditional yellow floor stand signs. These are available at the entrances to the first and second floor computer rooms at the Feynman Computing Center. At Wilson Hall, they can be found at the main entrance to the eighth floor Fiber Central room. They are also available near the entrances at GCC and LCC Computing Centers. You should use these markers to form a perimeter around open tiles in a manner that clearly and unmistakably defines the work area. Be sure to define an area of adequate size for the work to be done. In addition and not often remembered, it is often difficult to distinguish loose floor tiles from the surrounding floor. Therefore, floor tiles that have been removed must be kept within the work zone and clearly marked by placing a safety marker on top of them. Failure to follow this rule can result in serious injury to fellow workers. Violation of this rule may require an explanation to our Division Head.

Note: If you see an unmarked, open floor area in any of these rooms, please immediately place cones around it and on any loose floor tiles. Then notify Help Desk at x2345.

[computer.jpg](#)



For assistance contact helpdesk@fnal.gov
Mail comments about this page to cdweb@fnal.gov
EG 10/30/06